

City of Ottawa
CP000303
Form of Tender
Appendix FOT-F - Schedule of Items and Unit Prices
(all prices excluding H.S.T.)

Add No.	Item	Description	Unit	Quantity	Unit Bid Price	Total Bid Price
SECTION A						
GENERAL						
A-0001		Field office for Contract Administrator 20-34 m2 F-1001	wk	12.00		
A-0002		Traffic Control Plan F-1010, F-0303-01	LS	1.00		
A-0003		Supply, Maintain, and Remove Portable Variable Message Sign (PVMS) F-1019, F-0303-01	wk	12.00	1,600.00	19,200.00
A-0004		Construction Site Pedestrian Control Plan F-1013, F-0303-30	LS	1.00		
A-0005		Erosion and sediment control plan and monitoring 805, F-1004, F-0303-03	LS	1.00		
A-0006		Erosion and sediment control measures 805, F-1004, F-0303-03	LS	1.00		
A-0007		Pre-Construction Inspection F-1011, F-0303-08	LS	1.00		
A-0008		Sewer Flow Management Plan F-1007,	LS	1.00		
A-0009		Contract Initiation (should be no more than 2% of Total Tender Price) F-1006,	LS	1.00		
A-0010		Temporary Granular A Ramps and Sidewalk F-0303-28	t	30.00		
A-0011		Remove, Store & Reinstall Signs and Posts F-0303-04	LS	1.00		
A-0012		1.8m (ht) Steel Interlocking Construction Fencing & Gates F-0303-02	m	120.00		
A-0013		Watermain Vibration Monitoring F-0303-06	LS	1.00		
A-0014		Watermain Shutdown Contingency Plan F-0303-07	LS	1.00		
A-0015		Deductions for non-conformance related to QA/ QC submissions	LS	1.00	1.00	1.00
A-0016		ERS F-3130 Penalty F-3130	LS	1.00	1.00	1.00
A-0017		ERS F-3130 Bonus F-3130	LS	1.00	1.00	1.00
A-0018		F-3130 Bid AC F-3130	LS	1.00	1.00	1.00
A-0019		AC Price Index F-3101 F-3101	LS	1.00	1.00	1.00
A-0020		Cost of Referee Testing F-3130 F-3130	LS	1.00	1.00	1.00
SECTION A Total						

City of Ottawa
CP000303
Form of Tender
Appendix FOT-F - Schedule of Items and Unit Prices
(all prices excluding H.S.T.)

Add No.	Item	Description	Unit	Quantity	Unit Bid Price	Total Bid Price
SECTION B						
STORM SEWERS						
B-0001		1200mm dia. Storm maintenance hole per OPSD-701.010 407, 517, 518, F-4070, F-0303-13	ea (P)	1.00	_____	_____
B-0002		2440mm x 3050mm Storm Maintenance hole 407, 517, 518, F-4070, F-0303-16	ea (P)	1.00	_____	_____
B-0003		300 mm Concrete pipe storm sewer - class 140D 410, 517, 518, F-4100, F-0303-15	m	8.00	_____	_____
B-0004		375 mm Concrete pipe storm sewer - class 140D 410, F-4100, F-0303-14	m (P)	10.00	_____	_____
B-0005		Connection into Existing Storm Maintenance holes, Catch Basins, Ditch Inlets, Culverts and Sewers 410, 517, 518, F-4101	ea	2.00	_____	_____
B-0006		Cleaning and Televisе Sewers 409, 517, 518, F-4090, F-0303-27	m	250.00	_____	_____
B-0007		Miscellaneous 30MPa Concrete, Formed, where not otherwise provided 904, F-9040, F-9045,	m3	10.00	_____	_____
B-0008		Breaking into and Connection into Existing Storm Maintenance Holes, Catch Basins, Ditch Inlets, Culverts and Sewers 410, 517, 518, F-4101	ea (P)	1.00	_____	_____
B-0009		Construction of Work Areas and Protection for Underground Utilities F-0303-10	LS	1.00	_____	_____
B-0010		Cutting, Removal and Disposal of the existing 300mm Concrete Storm Sewer between MHST11198 and the new 1500mm Storm Sewer Pipe 517, 518, F-0303-15	m	4.00	_____	_____
B-0011		Supply and Install 200mm PVC Catch Basin Lead, Class SDR35 between the South-East Catch Basin and MHST11998 517, 518, F-0303-15	m	3.00	_____	_____
B-0012		Install High Early Strength 30MPa Concrete Plug in the 300mm Concrete Storm Pipe from the inside of the 1800mm CSP F-0303-15	m3	0.50	_____	_____
B-0013		Supply & Place Flowable Unshrinkable Backfill Material in the remaining 300mm Concrete Storm Sewer F-0303-15	m3	1.00	_____	_____
B-0014		Supply & Place Flowable Unshrinkable Backfill Material in 300mm Concrete Storm Sewer Trench F-0303-15	m3	50.00	_____	_____
B-0015		1500mm Concrete Pipe Storm Sewer-Class 140D by TBM & Pipe Jacking, including Water Resistant Shoring Walls 517, 518, F-0303-11	m	40.00	_____	_____
B-0016		1500mm Concrete Pipe Storm Sewer-Class 140D by Open Cut 517, 518, F-0303-25	m	16.00	_____	_____
B-0017		Temporary Water Tight Interlocking Steel Panel Water Diversion Walls 517, 518, F-0303-25	m2	140.00	_____	_____
B-0018		Precast Concrete Headwall for 1500mm Concrete Storm Sewer-Class 140D by Open Cut 517, 518, F-0303-12	ea	2.00	_____	_____
B-0019		Water Diversion and Dewatering Systems 517, 518, F-0303-17	LS	1.00	_____	_____
B-0020		1200mm Concrete Storm Sewer-Class 140D by Open Cut 517, 518, F-0303-26	m	25.00	_____	_____

City of Ottawa
CP000303
Form of Tender
Appendix FOT-F - Schedule of Items and Unit Prices
(all prices excluding H.S.T.)

Add No.	Item	Description	Unit	Quantity	Unit Bid Price	Total Bid Price
B-0021		Precast Concrete Headwall for 1200mm Concrete Storm Sewer by Open Cut 517, 518, F-0303-12	LS	1.00	_____	_____
B-0022		Abandonment of Storm Sewer Infrastructure 517, 518, F-0303-18	LS	1.00	_____	_____
B-0023		Supply and Place Flowable Unshrinkable Fill Material in the Remaining Composite Culvert System F-0303-18	m3	110.00	_____	_____
B-0024		Remove and Dispose of Existing Concrete Headwall for the 375mm Concrete Storm Sewer 517, 518, F-0303-14	LS	1.00	_____	_____
B-0025		Cut, Remove and Dispose of the existing section of 375mm storm pipe section between the new 1200mm MHST No. 201 and the existing headwall 401, 517, 518, F-0303-14	m	12.00	_____	_____
B-0026		Additional Excavation and Backfill with 50mm Clear Stone with and Geotextile Fabric Wrap, Non-Woven, Class II, FOS 75um 401, 517, 518, F-0303-20	m3	30.00	_____	_____
B-0027		Clay Seal for Storm Sewer Pipe 902, F-0303-24	ea	3.00	_____	_____
B-0028		Geogrid (bidirectional) F-0303-32	m2	250.00	_____	_____
SECTION B Total						_____

City of Ottawa
CP000303
Form of Tender
Appendix FOT-F - Schedule of Items and Unit Prices
(all prices excluding H.S.T.)

Add No.	Item	Description	Unit	Quantity	Unit Bid Price	Total Bid Price
SECTION C						
ROADS						
C-0001		Saw-cutting of asphalt 510,	m	17.00	_____	_____
C-0002		Remove Asphalt Pavement - Full Depth (Stripping) 510,	m2	15.00	_____	_____
C-0003		Granular 'A' 314, 501, F-3147, F-0303-15	t	15.00	_____	_____
C-0004		Water for dust suppression 506,	m3	50.00	_____	_____
C-0005		Asphalt Sidewalks, medians, boulevards and islands 311, F-3110,	m2	25.00	_____	_____
C-0006		Performance Graded Superpave 12.5mm Level B (PG 58-34) F-3101, F-3106, F-3130, F-0303-15	t	3.00	_____	_____
C-0007		Performance Graded Superpave 19mm Level B (PG 58-34) F-3101, F-3106, F-3130, F-0303-15	t	7.00	_____	_____
C-0008		Clearing, Grubbing and Removal of Stones, Rocks and Boulders 201, 510, F-0303-09	m2	225.00	_____	_____
C-0009		Salvaged and Stockpiled Select Native Materials for Backfilling, Grading and Shaping 206, 510, F-2120, F-0303-19	m2	600.00	_____	_____
C-0010		Geotextile Fabric, Non-Woven, Class II, FOS 75 Å Å Å µm 511, F-0303-20	m2	700.00	_____	_____
C-0011		Rip Rap, UngROUTED (210mm-375mm) Total Thickness 450mm 511, F-0303-21	m2	375.00	_____	_____
C-0012		Riverstone, Handlaid (75mm -125mm) Total Thickness 200mm 511, F-0303-21	m2	375.00	_____	_____
C-0013		650mm-1050mm Nominal Dimension Riverstone Boulders, Supplied and Placed F-0303-22	ea	10.00	_____	_____
C-0014		Decommissioning of Monitoring Well F-0303-23	LS	1.00	_____	_____
C-0015		Earth borrow 212	t	200.00	_____	_____
SECTION C Total						_____

City of Ottawa
CP000303
Form of Tender
Appendix FOT-F - Schedule of Items and Unit Prices
(all prices excluding H.S.T.)

Add No.	Item	Description	Unit	Quantity	Unit Bid Price	Total Bid Price
SECTION D						
LANDSCAPING						
D-0001		Barrier for tree protection 801, F-8011, F-0303-31	m	250.00		
D-0002		Topsoil, imported (100 mm thick) 802, F-8021,	m3	250.00		
D-0003		Sodding, staked or unstaked 803, F-8031,	m2	2,000.00		
D-0004		Water for Sod 803, F-8031,	m3	300.00		
D-0005		Bed Cover F-8043, F-0303-29	m2	350.00		
D-0006		Cornus stolonifera 60 cm (ht) supplied in peat or plastic pots F-8043, F-8047, F-0303-29	ea	32.00		
D-0007		Physocarpus opulifolius 60 cm (ht) supplied in peat or plastic pots F-8043, F-8047, F-0303-29	ea	32.00		
D-0008		Viburnum lentago 60 cm (ht) supplied in peat or plastic pots F-8043, F-8047, F-0303-29	ea	32.00		
D-0009		Acer rubrum 70 mm (dia) wire basket F-8043, F-8047, F-0303-29	ea	4.00		
D-0010		Acer saccharinum 70 mm (dia) wire basket F-8043, F-8047, F-0303-29	ea	4.00		
D-0011		Juglans nigra 70 mm (dia) wire basket F-8043, F-8047, F-0303-29	ea	4.00		
D-0012		Quercus macrocarpa 70 mm (dia) wire basket F-8043, F-8047, F-0303-29	ea	4.00		
D-0013		Extended Maintenance and Warranty Period for Planting F-8024,	LS	1.00		
D-0014		Highbush-Cranberry 60cm (ht) (Viburnum trilobum) supplied in 1 gallon plastic pot. (Riparian) F-8043, F-8047, F-0303-29	ea	32.00		
D-0015		Chokeberry 60cm (ht) (Aronia melanocarpa) supplied in 1 gallon plastic pot F-8043, F-8047, F-0303-29	ea	32.00		
D-0016		Bebb's Willow 100cm (ht) (Salix babbiana) supplied in 2 gallon plastic pot. (Riparian) F-8043, F-8047, F-0303-29	ea	12.00		
D-0017		Sandbar Willow 100cm (ht) (Salix exigua) supplied in 2 gallon plastic pot. (Riparian) F-8043, F-8047, F-0303-29	ea	12.00		
D-0018		Temporary Tree Removal, Temporary Planting of Tree and Replanting of Tree F-8043, F-8047, F-0303-05, F-0303-29	ea	4.00		
D-0019		Mulch -FIBRAMULCH SC32 for Shrub (Riparian) and Willow Plantings F-0303-29	m2	350.00		
D-0020		Mulch - Loose Composted Woodchip Material (75mm thk) for Tree Plantings (Replacement Trees) F-0303-29	m2	70.00		
D-0021		Tree and Shrub Fertilization F-8047	ea	204.00		
SECTION D Total						

City of Ottawa
CP000303
Form of Tender
Appendix FOT-F - Schedule of Items and Unit Prices
(all prices excluding H.S.T.)

Add No.	Item	Description	Unit	Quantity	Unit Bid Price	Total Bid Price
SECTION E						
LABOUR & EQUIPMENT						
E-0001		Sweeper (Operated) 127, F-8028	hr	50.00	<u>140.00</u>	<u>7,000.00</u>
E-0002		Flusher (Operated) 127, F-8028	hr	50.00	<u>141.00</u>	<u>7,050.00</u>
SECTION E Total						<u> </u>
Grand Total						<u> </u>

City of Ottawa
CP000303
Form of Tender
Appendix FOT-F - Schedule of Items and Unit Prices
(all prices excluding H.S.T.)

Summary of Tender(Excluding HST)	Total
SECTION A	
GENERAL Total	
SECTION A Total	
SECTION B	
STORM SEWERS Total	
SECTION B Total	
SECTION C	
ROADS Total	
SECTION C Total	
SECTION D	
LANDSCAPING Total	
SECTION D Total	
SECTION E	
LABOUR & EQUIPMENT Total	
SECTION E Total	
Grand Total	