

QUANTITY SHEETS

CONTRACT NO. 2020-5153

BOOK 1 OF 1

**NORTH REGION**

**NORTHEAST**

Ministry Of Transportation



# INDEX

W.P. No. 5144-10-00

Contract No. 2020-5153

Sheet No.	Description
	CONTRACT DRAWINGS - BOOK 1 OF 1
	TITLE SHEET (KEY PLAN)
	INDEX SHEET
	NEBSKWASHI RIVER BRIDGE - SITE 46X-0236/B0
1-2	HORIZONTAL & VERTICAL CONTROL
3	STAGING
4	REMOVALS
5	NEW CONSTRUCTION
6	GRADING DETAILS
7	SIGN TABLE
8-11	ELECTRICAL
12-27	STRUCTURAL
	NEMEGOSENDA RIVER BRIDGE - SITE 46X-0215/B0
28	HORIZONTAL & VERTICAL CONTROL
29-30	STAGING
31	REMOVALS
32-33	NEW CONSTRUCTION
34-37	GRADING DETAILS
38	SIGN TABLE
39-42	ELECTRICAL
43-65	STRUCTURAL
	SIDEBURNED RIVER BRIDGE - SITE 46X-0015/B0
66	HORIZONTAL & VERTICAL CONTROL
67-68	STAGING
69	REMOVALS
70	NEW CONSTRUCTION
71-72	GRADING DETAILS

Sheet No.	Description
73	SIGN TABLE
74-77	ELECTRICAL
78-99	STRUCTURAL
	QUANTITY SHEETS - BOOK 1 OF 1
	NEBSKWASHI RIVER BRIDGE - SITE 46X-0236/B0
1-14	GRADING
15-20	ELECTRICAL
21-23	STRUCTURAL
	NEMEGOSENDA RIVER BRIDGE - SITE 46X-0215/B0
24-40	GRADING
41	ELECTRICAL
42-43	STRUCTURAL
	SIDEBURNED RIVER BRIDGE - SITE 46X-0015/B0
44-61	GRADING
62-65	ELECTRICAL
66-67	STRUCTURAL



**QUANTITIES - HOT MIX AND GRANULAR**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
2

MINISTRY OF TRANSPORTATION - ONTARIO

Description	Superpave 12.5 [40mm Surface Course]	Superpave 12.5 [40mm Binder Course]	Superpave 12.5 [50mm Binder Course]		Granular A [Roadway & Shoulder]	Granular A [Concrete Curb & Gutter]	Granular A [Bedding and Backfill]		RAP Shouldering							References
Sub - Totals Brought Forward:																
Highway 129																
Township of Chapleau																
Nebskwashi River Bridge																
Site No. 46X-0236/B0																
20+434 - 20+476	35															
20+434 - 20+495 Lt									66							
20+455 - 20+497 Rt									42							
20+476 - 20+504	25		32													
20+491 - 20+498 Lt						5										
20+493 - 20+500 Rt						5										
20+504 - 20+516	10	10														
20+516 - 20+545	28		32													
20+521 - 20+548 Lt									27							
20+524 - 20+549 Rt									27							
20+545 - 20+598	47															
20+555 - 20+600 Lt									46							
20+558 - 20+601 Rt									41							
20+476 - 20+499					150											
20+521 - 20+545					157											
20+545 - 20+559 Rt (Entrance)					22											
Sub - Totals Carried Forward:																
	145	10	64		329	10	0		249							
<b>TOTALS</b>																
UNIT	t	t	t		t	t	t		m2							
ITEM No.		6				7			8							
Reference																
Remarks:																

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_

Hot Mix and Granular





**QUANTITIES - PIPE CULVERTS**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
5

Culvert No	Station	Location and Position	Ext		Skew No	End Finish	Depth to Pipe	Pipe Fill Material			Pipe Joints	Treatment	Inv Elev		500 mm Pipe Culvert 500 + 100 S 000111 500 + 100 C 000111	References
			Left	Right				Bedding	Cover	Backfill			Upstream	Downstream		
Sub - Totals Brought Forward:																
		Nebskwashi River Bridge Highway 129														
1	20+551	9.32m Lt	9.32	1				A	A	G	L			14		
2	20+552	8.80m Rt	0	8.8				A	A	G	L			14		
Sub - Totals Carried Forward:																
														28		

MINISTRY OF TRANSPORTATION - ONTARIO

**Pipe Material Code - 6 digits defined as noted below:**

- 1st digit = Concrete**  
 1 - 50-D or HE-A  
 2 - 65-D or HE-I  
 3 - 100-D or HE-II  
 4 - 140-D or HE-III  
 5 - HE-IV
- 2nd digit = PVC/PP**  
 1 - PVC  
 2 - PP
- 3rd digit = HDPE**  
 1 - Open Profile  
 2 - Closed Profile
- 4th digit = Galv; 5th digit = Alum, & 6th digit = Polymer Steel**  
 1 - 1.6 mm thick  
 2 - 2.0 mm thick  
 3 - 2.8, 3.0 & 3.18 mm thick  
 4 - 3.5, 3.81 & 4.0 mm thick  
 5 - 4.2, 4.45 & 5.0 mm thick  
 6 - 5.08 & 6.0 mm thick  
 7 - 5.72 & 7.0 mm thick  
 8 - 6.35 mm thick
- Note:** '0' for any digit means the pipe material is not acceptable.  
 Higher pipe material code values are also acceptable, unless otherwise stated. Galv. means galvanized coating.  
 Alum means aluminized coated or aluminum alloy materials.  
 Polymer means both laminated and coated steel pipes.  
 Applies to circular and non-circular pipes.

**Pipe Type**

- S** - Smooth inner wall pipe  
**C** - Corrugated inner wall pipe

**Pipe Joints**

- S** - Soil tight  
**F** - Silt/Fines tight  
**L** - Leak tight

**Note:** S joints is specified if no code is entered.

**End Finish (OPSD 801.01 - 02 - 03)**

- SqE** - Square End  
**B** - Bevel  
**Sk** - Skew End  
**SB** - Step Bevel  
**ES** - Steel end section

**Note:** All pipes are SqE and symmetrical to CL unless otherwise stated.

**Treatments**

- F** - Frost Treatment  
**P** - Pave Invert  
**S** - Channel Substrate  
**B** - Fish Baffles

**Depth to Pipe** is from the surface downward to top of base pipe opening at midpoint by length unless otherwise stated.

**Pipe Fill Material**

- N** - Native or Granular  
**G** - Granular A or B Type I, II or III  
**B** - Granular A or B Type II  
**A** - Granular A  
**U** - Unshrinkable fill

**Notes:** N applies to cover and backfill only.  
 1 letter specifies material for all pipes.  
 2 letter codes specifies fill material for rigid and flexible pipes respectively.  
 G for bedding and N for cover and backfill is specified if no code is entered.  
 Embedment material for flexible pipes specified in bedding material column.

**Frost Penetration**

Frost Penetration depth - 1.5 m

	(P)								
<b>TOTALS</b>	28								
<b>UNIT</b>	m (P)								
<b>ITEM No.</b>	11								

CHKD. \_\_\_\_\_  
 APPR. \_\_\_\_\_  
 DATE \_\_\_\_\_

Pipe Culverts











**QUANTITIES - MISCELLANEOUS 1**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
10

MINISTRY OF TRANSPORTATION - ONTARIO

Location and Position		Small Signs, Ground Mounted, New		Small Signs, Removal		Temporary Traffic Control Signs		Road Closing / Restriction Notice Signs (TC-64)					References
Sub - Totals Brought Forward:													
Highway 129													
Township of Chapleau													
Nebskwashi River Bridge													
Site No. 46X-0236/B0													
Throughout Contract Limits						100 %		4					
20+070 (Wa3L, Wa7t)				1									
20+070 (Wa103L, Wa7t)		1											
20+134 (N/A)				1									
20+134 (Wa-111, Wa-18t (B), Wa-23t (250m))		1											
20+409 (N/A)				1									
20+409 (Wa-73)		1											
20+409 (N/A)				1									
20+409 (Wa8)		1											
20+484 (Wa3R)				1									
20+484 (Wa103R)		1											
20+500 (Wa33R)				1									
20+524 (G331)				1									
20+524 (G331(B))		1											
20+534 (Wa33L)				1									
20+948 (Wa3L, Wa7t)				1									
Sub - Totals Carried Forward:													
		6		9		100 %		4					
		(P)		(P)				(P)					
TOTALS													
UNIT		each (P)		each (P)		lump sum		each (P)					
ITEM No.		24		25		26		27					
Reference													
													CHKD. _____ APPR. _____ DATE _____

QUANTITIES - MISCELLANEOUS 1

W.P. No. 5144-10-00  
Contract No. 2020-5153

Location and Position		Small Signs, Ground Mounted, New		Small Signs, Removal		Temporary Traffic Control Signs		Road Closing / Restriction Notice Signs (TC-64)					References
Sub - Totals Brought Forward:		6		9		100 %		4					
20+948 (Wa103L, Wa7t)		1											
20+610 (N/A)				1									
20+610 (Wa-111, Wa-18t (B), Wa-23t (250m))		1											
20+544 (Wa3R)				1									
20+544 (Wa103R)		1											
20+521 (Wa33R)				1									
20+498 (Wa33L)				1									
20+495 (G331)				1									
20+495 (G331(B))		1											

**QUANTITIES - MISCELLANEOUS 1**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
12

MINISTRY OF TRANSPORTATION - ONTARIO

Location and Position	Pavement Marking Obliterating - By Abrasive Blasting		Pavement Marking [Solid] [White, 10cm]	Pavement Marking [Solid Double] [Yellow, 10cm]		Pavement Marking, Temporary [Solid] [White, 10cm]	Pavement Marking, Temporary [Solid] [White, 10cm]	Pavement Marking, Temporary [Solid] [White, 60cm]					References
Sub - Totals Brought Forward:													
Highway 129													
Township of Chapleau													
Nebskwashi River Bridge													
Site No. 46X-0236/B0													
Pre-Stage 1													
20+409 - 20+434 CI						25							
20+434 Rt								21					
20+444 - 20+454 Rt								70					
20+409 - 20+623 Lt/CI/Rt								712					
20+598 Lt								21					
20+598 - 20+623 CI						25							
Stage 1													
20+434 - 20+498 Rt	65							65					
20+434 - 20+600 Lt	165							165					
20+522 - 20+600 Rt	78							78					
Stage 2													
20+434 - 20+498 Lt	64							64					
20+434 - 20+600 Rt	166							166					
20+522- 20+600 Lt	79							79					
Final Road Construction													
20+434 - 20+600 Lt/Rt			331										
20+409 - 20+623 CI				428									
Sub - Totals Carried Forward:													
	617		331	428		50	1,329	112					
	(P)		(P)	(M)		(P)	(M)	(P)					
<b>TOTALS</b>	617		331	428		50	1,329	112					
<b>UNIT</b>	m (P)		m (P)	m (P)		m (P)	m (P)	m (P)					
<b>ITEM No.</b>	28			29			30						
<b>Reference</b>													

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_

Pavement Markings

**QUANTITIES - MISCELLANEOUS 1**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
13

MINISTRY OF TRANSPORTATION - ONTARIO

Location and Position	Single Rail SBGR with Channel [OPSD 912.315]	Single Rail SBGR, TL-3 [OPSD 912.185]		Energy Attenuator - Temporary, Narrow [TL-2]	Energy Attenuator - Relocation, Narrow [TL-2]		SBEAT System [50:1 Flare]	Steel Beam Energy Attenuating Terminal System [Parallel to Roadway]		TCB, Freestanding, Category IV	Temporary Construction Barrier, Relocation		References
Sub - Totals Brought Forward:													
Highway 129 Township of Chapleau													
Nebskwashi River Bridge Site No. 46X-0236/B0													
20+473 Rt							1						
20+473 - 20+480 Rt (Offset 3.6m - 3.7m Rt)		8											
20+474 Lt							1						
20+474 - 20+478 Lt (Offset 5.3m - 5.1m Lt)			8										
20+478 - 20+498 Lt (Offset 5.1 - 4.5m Lt)		20											
20+480 - 20+500 Rt (Offset 3.7m - 4.1m Rt)		20											
20+525 - 20+537 Lt (Offset 4.7m - 4.5m Lt)		16											
20+524 - 20+540 Rt (Offset 4.8m - 5.0m Rt)		16											
20+537 Lt								1					
20+540 Rt								1					
Stage 1 20+462 Rt				1									
20+462 - 20+554 Rt									92				
20+554 Rt				1									
Stage 2 20+466 Lt					1								
20+466 - 20+562 Lt									4		92		
20+562 Lt					1								
Sub - Totals Carried Forward:	72	16		2	2		2	2		96	92		
	(P)	(P)		(P)	(P)		(P)	(P)		(P)	(P)		
<b>TOTALS</b>	72	16		2	2		2	4		96	92		
<b>UNIT</b>	m (P)	m (P)		each (P)	each (P)		each (P)	each (P)		m (P)	m (P)		
<b>ITEM No.</b>	31	32		33	34		35	35		36	37		
<b>Reference</b>													

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_

SBGR and TCB





**QUANTITIES - TEMPORARY INSTALLATION**

W.P. No. 5144-10-00

Contract No. 2020-5153

Location	Structure/Equipment No.	Offset (m) to CL of Structure/Equip't (Note 1)	Signal Head Facing Direction	From - To OR Station	Distance (m)	Maintenance and Operation for Temporary Traffic Signal System Work	#2 AWG, 2-Cond., NSF-2 Low Voltage Cables, Aerial with ACSR Neutral [Temporary]	#6 AWG Low Voltage Cables Aerial on Messenger Cable [Temporary]	12-Cond. Traffic Signal Cables Aerial on Messenger Cable [Temporary]	7 mm, Grade 110 Steel Messenger Cables Aerial [Temporary]	9 mm, Grade 160 Steel Messenger Cables Aerial [Temporary]	#6 AWG, Insulated, Ground Wire [Temporary]	#6 AWG, Bare, Ground Wire [Temporary]	#2/0 AWG, Bare, Ground Wire [Temporary]	Ground Electrodes [Temporary] [Rods]	Supply Control Cabinet Assemblies [Temporary] Type 3, 1Ph 120/240 V, [OPSD 2441.000]	14 m, Class 4 Wood Poles Direct Buried in Earth [Temporary]	12.5 m, Class 4 Wood Poles Direct Buried in Earth [Temporary]
Sub - Totals Brought Forward:																		
Highway 129 Township of Chapleau																		
Nebskawashi River Bridge Site No. 46X-0236/B0						100 %												
Highway 129	P1	6.0		20+466.5										20	4	1	1	
Highway 129	P2	10.1		20+466.5														1
Highway 129	P3	9.9		20+437.5									1		1		1	
Highway 129	P4	10.2		20+496.4														
Highway 129	P5	10.2		20+528														
Highway 129	P6	10.2		20+562									1		1			
Highway 129	P7	8.8		20+562									1		1			
Highway 129	P8	3.2*	W	20+798														
Highway 129	P9	3.2*	E	20+234														
Highway 129				EP1-P1	13		13											
Highway 129			E	P1-P2	16			64	16	16	16	16	16					
Highway 129			N	P2-P3	28			56		28	28							
Highway 129				P1-P4	31			62	31		31							
Sub - Totals Carried Forward:						100 %	13	182	47	44	75	16	3	20	7	1	2	1
							(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)
TOTALS																		
UNIT						lump sum	m (P)	m (P)	m (P)	m (P)	m (P)	m (P)	m (P)	m (P)	each (P)	each (P)	each (P)	each (P)
ITEM No.						41	42	43	44	45	46	47	48	49				
Remarks:						Note: 1 When shown without *, offset is from centre or control line of roadway. When shown with *, offset is from edge of travelled pavement (EP).										CHKD. _____ APPR. _____ DATE _____		

MINISTRY OF TRANSPORTATION - ONTARIO

Temporary - Nebskawashi River Bridge

**QUANTITIES - TEMPORARY INSTALLATION**

W.P. No. 5144-10-00

Contract No. 2020-5153

SHEET

MINISTRY OF TRANSPORTATION - ONTARIO

Location	Structure/Equipment No.	Offset (m) to CL of Structure/Equip't (Note 1)	Signal Head Facing Direction	From - To OR Station	Distance (m)	5.0 m, Class - Wood Poles Direct Buried in Earth [Temporary] <sup>1</sup>	14.0 m, Class 4 Wood Poles Direct Buried in Rock [Temporary]	12.5 m, Class 4 Wood Poles Direct Buried in Rock [Temporary]	5.0 m, Class - Wood Poles Direct Buried in Rock [Temporary] <sup>1</sup>	Guy Anchors (Temporary)	400W HPS Luminaire, 120 V Ballast c/w 200 W HPS Lamp [Temporary]	2.4 m Al. Tapered Elliptical Bracket	#12 AWG Riser Wires 3 Wires/Pole	Highway Type Signal Heads (Temporary) <sup>2</sup>	Riser Wires #14 AWG, 5/C	Flasher Beacons [Temporary] [Detail] <sup>3</sup>	Riser Wires #12 AWG, 2/C	Traffic Signal Controllers [Temporary] [OPSD 2510.010 & MTOD 2510.007]	
Sub - Totals Brought Forward:																			
Highway 129 Township of Chapleau																			
Nebskawashi River Bridge Site No. 46X-0236/B0																			
Highway 129	P1	6.0		20+466.5						2	1	1	5						
Highway 129	P2	10.1		20+466.5						2								1	
Highway 129	P3	9.9		20+437.5						1	1	1	5						
Highway 129	P4	10.2		20+496.4				1		2									
Highway 129	P5	10.2		20+528				1											
Highway 129	P6	10.2		20+562				1		2									
Highway 129	P7	8.8		20+562			1				1	1	5						
Highway 129	P8	3.2*	W	20+798					1									1	
Highway 129	P9	3.2*	E	20+234		1												1	
Highway 129				EP1-P1	13														
Highway 129			E	P1-P2	16									2	22.0				
Highway 129			N	P2-P3	28									2	38.0				
Highway 129				P1-P4	31														
Sub - Totals Carried Forward:						1	1	3	1	9	3	3	15	4	60.0	2	0	1	
						(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	
TOTALS																			
UNIT						each (P)	each (P)	each (P)	each (P)	each (P)	each (P)	each (P)	m (P)	each (P)	m (P)	each (P)	m (P)	each (P)	
ITEM No.								50		51	52			53		54		55	
Remarks: 1. 150mm x 150mm x 5m Pressure Treated Wood Post.						2. All 300mm Lenses in Diameter.						Note: 1 When shown without *, offset is from centre or control line of roadway. When shown with *, offset is from edge of travelled pavement (EP).						CHKD. _____	
3. 300mm Flasher Beacon with Solar Powered System.						4. Traffic Signal Controller c/w UPS System.												APPR. _____	
																		DATE _____	

Temporary - Nebskawashi River Bridge

**QUANTITIES - TEMPORARY INSTALLATION**

W.P. No. 5144-10-00  
Contract No. 2020-5153

Location	Structure/Equipment No.	Offset (m) to CL of Structure/Equip't (Note 1)	Signal Head Facing Direction	From - To OR Station	Distance (m)	Non-Intrusive Detection System (Temporary)	Non-Intrusive Detectors	Non-Intrusive Detection Cables <sup>5</sup>										
Sub - Totals Brought Forward:																		
Highway 129 Township of Chapleau																		
Nebskawashi River Bridge Site No. 46X-0236/B0						1												
Highway 129	P1	6.0		20+466.5			1	21										
Highway 129	P2	10.1		20+466.5			1	8										
Highway 129	P3	9.9		20+437.5														
Highway 129	P4	10.2		20+496.4														
Highway 129	P5	10.2		20+528														
Highway 129	P6	10.2		20+562														
Highway 129	P7	8.8		20+562			1	135										
Highway 129	P8	3.2*	W	20+798														
Highway 129	P9	3.2*	E	20+234														
Highway 129				EP1-P1	13													
Highway 129			E	P1-P2	16													
Highway 129			N	P2-P3	28													
Highway 129				P1-P4	31													
Sub - Totals Carried Forward:						1	3	164										
(P)																		
TOTALS																		
UNIT						each (P)	each	m										
ITEM No.						56												

MINISTRY OF TRANSPORTATION - ONTARIO

Temporary - Nebskawashi River Bridge

Remarks<sup>5</sup>. Non-Intrusive Detection Cable as per Manufacturer's Recommendations.

Note: 1 When shown without \*, offset is from centre or control line of roadway.  
When shown with \*, offset is from edge of travelled pavement (EP).

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_

**QUANTITIES - TEMPORARY INSTALLATION**

W.P. No. 5144-10-00

Contract No. 2020-5153

Location	Structure/Equipment No.	Offset (m) to CL of Structure/Equip't (Note 1)	Signal Head Facing Direction	From - To OR Station	Distance (m)	Maintenance and Operation for Temporary Traffic Signal System Work	#2 AWG, 2-Cond., NSF-2 Low Voltage Cables, Aerial with ACSR Neutral [Temporary]	#6 AWG Low Voltage Cables Aerial on Messenger Cable [Temporary]	12-Cond. Traffic Signal Cables Aerial on Messenger Cable [Temporary]	7 mm, Grade 110 Steel Messenger Cables Aerial [Temporary]	9 mm, Grade 160 Steel Messenger Cables Aerial [Temporary]	#6 AWG, Insulated, Ground Wire [Temporary]	#6 AWG, Bare, Ground Wire [Temporary]	#2/0 AWG, Bare, Ground Wire [Temporary]	Ground Electrodes [Temporary] [Rods]	Supply Control Cabinet Assemblies [Temporary] Type 3, 1Ph 120/240 V, [OPSD 2441.000]	14 m, Class 4 Wood Poles Direct Buried in Earth [Temporary]	12.5 m, Class 4 Wood Poles Direct Buried in Earth [Temporary]	
Sub - Totals Brought Forward:						100 %	13	182	47	44	75	16	3	20	7	1	2	1	
Highway 129				P4-P5	32			64	32		32								
Highway 129				P5-P6	34			68	34		34								
Highway 129			W	P6-P7	19			38		19	19								
Sub - Totals Carried Forward:						100 %	13	352	113	63	160	16	3	20	7	1	2	1	
										63	160	16	3	20			2	1	
										(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	
TOTALS						100 %	13	352	113		223		39		7	1		4	
UNIT						lump sum	m (P)	m (P)	m (P)	m (P)	m (P)	m (P)	m (P)	m (P)	m (P)	each (P)	each (P)	each (P)	each (P)
ITEM No.						41	42	43	44		45		46		47	48		49	

MINISTRY OF TRANSPORTATION - ONTARIO

Temporary - Nebskawashi River Bridge

Remarks:

Note: 1 When shown without \*, offset is from centre or control line of roadway.  
When shown with \*, offset is from edge of travelled pavement (EP).

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_

**QUANTITIES - TEMPORARY INSTALLATION**

W.P. No. 5144-10-00

Contract No. 2020-5153

SHEET

Location	Structure/Equipment No.	Offset (m) to CL of Structure/Equip't (Note 1)	Signal Head Facing Direction	From - To OR Station	Distance (m)	5.0 m, Class - Wood Poles Direct Buried in Earth [Temporary] <sup>1</sup>	14.0 m, Class 4 Wood Poles Direct Buried in Rock [Temporary]	12.5 m, Class 4 Wood Poles Direct Buried in Rock [Temporary]	5.0 m, Class - Wood Poles Direct Buried in Rock [Temporary] <sup>1</sup>	Guy Anchors (Temporary)	400W HPS Luminaire, 120 V Ballast c/w 200 W HPS Lamp [Temporary]	2.4 m Al. Tapered Elliptical Bracket	#12 AWG Riser Wires 3 Wires/Pole	Highway Type Signal Heads (Temporary) <sup>2</sup>	Riser Wires #14 AWG, 5/C	Flasher Beacons [Temporary] [Detail] <sup>3</sup>	Riser Wires #12 AWG, 2/C	Traffic Signal Controllers [Temporary] [OPSD 2510.010 & MTOD 2510.007]
Sub - Totals Brought Forward:						1	1	3	1	9	3	3	15	4	60.0	2	0	1
Highway 129				P4-P5	32													
Highway 129				P5-P6	34													
Highway 129			W	P6-P7	19													
Sub - Totals Carried Forward:						1	1	3	1	9	3	3	15	4	60.0	2	0	1
						(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)
TOTALS								5		9	3			4		2		1
UNIT						each (P)	each (P)	each (P)	each (P)	each (P)	each (P)	each (P)	m (P)	each (P)	m (P)	each (P)	m (P)	each (P)
ITEM No.								50		51	52			53		54		55

MINISTRY OF TRANSPORTATION - ONTARIO

Temporary - Nebskawashi River Bridge

Remarks: 1. 150mm x 150mm x 5m Pressure Treated Wood Post.  
3. 300mm Flasher Beacon with Solar Powered System.

2. All 300mm Lenses in Diameter.  
4. Traffic Signal Controller c/w UPS System.

Note: 1 When shown without \*, offset is from centre or control line of roadway. When shown with \*, offset is from edge of travelled pavement (EP).

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_

**QUANTITIES - TEMPORARY INSTALLATION**

W.P. No. 5144-10-00  
Contract No. 2020-5153

Location	Structure/Equipment No.	Offset (m) to CL of Structure/Equip't (Note 1)	Signal Head Facing Direction	From - To OR Station	Distance (m)	Non-Intrusive Detection System (Temporary)	Non-Intrusive Detectors	Non-Intrusive Detection Cables <sup>5</sup>										
Sub - Totals Brought Forward:						1	3	164										
Highway 129				P4-P5	32													
Highway 129				P5-P6	34													
Highway 129			W	P6-P7	19													
Sub - Totals Carried Forward:						1												
(P)																		
TOTALS						1	3	164										
UNIT						each (P)	each	m										
ITEM No.						56												

MINISTRY OF TRANSPORTATION - ONTARIO

Temporary - Nebskawashi River Bridge

Remarks<sup>5</sup>. Non-Intrusive Detection Cable as per Manufacturer's Recommendations.

Note: 1 When shown without \*, offset is from centre or control line of roadway.  
When shown with \*, offset is from edge of travelled pavement (EP).

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_













QUANTITIES - MISCELLANEOUS 1

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
26

Location and Position	Tack Coat [Milled Surface]	Tack Coat [Binder Surface]											References
Sub - Totals Brought Forward:													
Highway 101													
Township of Chewett													
Nemegosenda River Bridge													
Site No. 46X-0215/B0													
14+021 - 14+094	658												
14+094 - 14+422		3,116											
14+422- 14+438	144												
	802	3,116											
	802	3,116											
	(P)	(P)											
		3,918											

**QUANTITIES - HOT MIX AND GRANULAR**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
27

MINISTRY OF TRANSPORTATION - ONTARIO

Description	Superpave 12.5 [Surface Course (40mm)]	Superpave 12.5 [Binder Course (40mm)]	Superpave 12.5 [Binder Course (50mm)]	Granular A [Roadway]	Granular A [Temporary Detour - Preloading]	Granular A [Temporary Detour]	Granular A [TMB Backfill & Padding]	Granular A [Structure Backfill]	Granular A [Concret Curb & Gutter]	Granular A, From Stockpile [End Area Method]		Granular B, Type II [Temporary Detour]	Granular B, Type II [Roadway]	Granular B, Type II [Backfill]	RAP Shouldering	References
<b>Sub - Totals Brought Forward:</b>																
Highway 101																
Township of Chewett																
Nemegosenda River Bridge																
Site No. 46X-0215/B0																
Temporary Detour - Year 1					577		748									
Temporary Detour Bridge - Year 2																
Stage 1										46						
10+000 - 10+120						561				97		3,124				
10+178 - 10+308						1,067				97		920				
Final Road Construction																
Highway 101																
14+021 - 14+219				1,611										1,432		
14+021 - 14+094 Lt (Left Shoulder)	8															
14+021 - 14+094 CL (Lanes)	52															
14+021 - 14+094 Rt (Right Shoulder)	8															
14+021 - 14+211 Lt															225	
14+021 - 14+211 Rt															328	
14+094- 14+219 Lt (Left Shoulder)	15		18													
14+094 - 14+219 CL (Lanes)	87		109													
14+094 - 14+219 Rt (Right Shoulder)	15		18													
14+211 - 14+220 Lt										7						
14+211 - 14+220 Rt										7						
Nemegosenda River Bridge																
14+219 - 14+261 Lt (Left Shoulder)	13	13							153						1,734	
14+219 - 14+261 CL (Lanes)	30	30														
14+219 -14+261 Rt (Right Shoulder)	13	13														
<b>Sub - Totals Carried Forward:</b>	241	56	145	1,611	577	1,628	748	153	14	240		4,044	1,432	1,734	553	
<b>TOTALS</b>																
UNIT	t	t	t	t	t	t	t	t	t	m3		t	t	t	m2	
ITEM No.		95			96					97			98		99	
Reference																
Remarks:																

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_

Hot Mix and Granular













**QUANTITIES - MISCELLANEOUS 1**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
33

MINISTRY OF TRANSPORTATION - ONTARIO

Location and Position	Removal of Concrete Curb and Gutter [Roadway]		Removal of Energy Attenuators [Eccentric Loader]		Removal of Steel Beam Guide Rail [Single Rail] [With Channel]	Removal of Steel Beam Guide Rail [Single Rail] [Without Channel]							References
Sub - Totals Brought Forward:													
Highway 101													
Township of Chewett													
Nemegosenda River Bridge													
Site No. 46X-0215/B0													
14+124 - 14+139 Lt			1										
14+124 - 14+139 Rt			1										
14+139 - 14+208 Lt						69							
14+139 - 14+208 Rt						69							
14+208 - 14+228 Lt					20								
14+208 - 14+228 Rt					20								
14+216 - 14+228 (Offset 5.2m - 4.8m Lt)	12												
14+216 - 14+288 (Offset 4.7m - 4.6m Rt)	12												
14+253 - 14+264 (Offset 4.5m - 4.3m Lt)	11												
14+253 - 14+273 Lt					20								
14+253 - 14+264 (Offset 4.9m - 4.7m Rt)	11												
14+253 - 14+273 Rt					20								
14+273 - 14+341 Lt						68							
14+273 - 14+340 Rt						68							
14+341 - 14+356 Lt			1										
14+340 - 14+355 Rt			1										
Sub - Totals Carried Forward:													
	46		4		80	274							
					80	274							
<b>TOTALS</b>	(P) 46		(P) 4		(P) 80	(M) 274							
<b>UNIT</b>	m (P)		each (P)		m (P)	m (P)							
<b>ITEM No.</b>	106		107			108							
<b>Reference</b>													
													CHKD. _____ APPR. _____ DATE _____

Removals

**QUANTITIES - MISCELLANEOUS 1**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
34

Location and Position	Rock Protection	Rip-Rap (R-10)	Geotextile (Class II) (Non-woven) (FOS 75-150 micron)									References
Sub - Totals Brought Forward:												
Highway 101												
Township of Chewett												
Nemegosenda River Bridge												
Site No. 46X-0215/B0												
Temporary Modular Bridge												
10+120 - 10+122 (Offset 2.5m - 6.4m Lt)		11	13									
10+122 - 10+139 (Offset 3.3m - 6.3m Lt)	29		53									
10+120 - 10+122 (Offset 2.4m - 4.6m Rt)		7	8									
10+122 - 10+139 (Offset 3.2m - 4.6m Rt)	12		28									
10+158 - 10+176 (Offset 3.2m - 6.0m Lt)	25		43									
10+158 - 10+176 (Offset 2.3m - 4.6m Rt)	13		28									
10+176 - 10+178 (Offset 2.5m - 6.0m Lt)		9	14									
10+176 - 10+178 (Offset 2.3m - 4.6m Rt)		7	7									
West Detour Abutment			140									
East Detour Abutment			190									
Highway 101												
14+219 - 14+230 (Offset 6.5m - 14.3m Lt)	43		82									
14+219 - 14+230 (Offset 6.5m - 10.2m Rt)	27		52									
14+251 - 14+261 (Offset 6.5m - 11.6m Lt)	34		65									
14+251 - 14+261 (Offset 6.5m - 11.6m Rt)	41		78									
14+297 (Offset 5.4m Lt - end of spillway)		10	15									
14+297 (Offset 5.2m Rt - end of spillway)		10	15									
Sub - Totals Carried Forward:												
	224	54	831									
	(P)	(P)	(P)									
TOTALS												
UNIT	m3 (P)	m2 (P)	m2 (P)									
ITEM No.	109	110	111									
Reference												

MINISTRY OF TRANSPORTATION - ONTARIO

Rip-Rap & Geotextile

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_





QUANTITIES - MISCELLANEOUS 1

W.P. No. 5144-10-00  
Contract No. 2020-5153

MINISTRY OF TRANSPORTATION - ONTARIO

Location and Position	Pavement Marking Obliterating - By Abrasive Blasting		Pavement Marking [Solid Double] [Yellow, 10cm]	Pavement Marking [Solid] [White, 10cm]		Pavement Marking, Temporary [Solid] [White, 60cm]		Temporary Raised Transverse Rumble Strips					References
Sub - Totals Brought Forward:													
Highway 101													
Township of Chewett													
Nemegosenda River Bridge													
Site No. 46X-0215/B0													
Stage 1													
13+766 - 13+780 Rt (Set of 8)													
13+980 - 13+989 Rt (Set of 8)													
14+089 - 14+401 (Between Stop Bars)													
14+089 Rt (Stop Bar)													
14+401 Lt (Stop Bar)													
14+502 - 14+511 Lt (Set of 8)													
14+716 - 14+730 Lt (Set of 8)													
Final Road Construction													
14+021 - 14+438 Lt/CL/Rt													

**QUANTITIES - MISCELLANEOUS**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
38

MINISTRY OF TRANSPORTATION - ONTARIO

Description	Single Rail SBGR with Channel [OPSD 912.315]	Single Rail SBGR, TL-3, Adjacent to 2H:1V Slope [OPSD 912.186]	Single Rail SBGR, TL-3, Adjacent to Curb and Gutter [OPSD 912.188]	TCB, Freestanding, Category II		Energy Attenuator - Temporary, Narrow [TL-3]	Energy Attenuator - Relocation, Narrow [TL-3]		SBEAT System [50:1 Flare]		Temporary Construction Barrier, Relocation		
Sub - Totals Brought Forward:													
Highway 101													
Township of Chewett													
Nemegosenda River Bridge													
Site No. 46X-0215/B0													
Stage 1													
14+092 Lt (Install on Concrete Pad)						1							
14+380 Lt (Install on Concrete Pad)						1							
14+092 - 14+380 Lt				288									
Stage 2													
14+093 Lt							1						
14+092 - 10+120 Lt											120		
10+020 - 10+120 Rt											100		
10+178 - 10+287 Lt				40							68		
10+178 - 10+270 Rt				92									
10+270 Rt (Install on Concrete Pad)						1							
10+287 Lt							1						
Final Road Construction													
14+138 Lt									1				
14+139 Rt									1				
Sub - Totals Carried Forward:													
	0	0	0	420		3	2		2		288		
	(P)	(P)	(P)	(P)		(P)	(P)		(P)		(P)		
TOTALS													
UNIT	m (P)	m (P)	m (P)	m (P)		each (P)	each (P)		each (P)		m (P)		
ITEM No.	120	121	122	123		124	125		126		127		

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_

SBGR & TCB



**QUANTITIES - MISCELLANEOUS**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
39

MINISTRY OF TRANSPORTATION - ONTARIO

Description	Single Rail SBGR with Channel [OPSD 912.315]	Single Rail SBGR, TL-3, Adjacent to 2H:1V Slope [OPSD 912.186]	Single Rail SBGR, TL-3, Adjacent to Curb and Gutter [OPSD 912.188]	TCB, Freestanding, Category II		Energy Attenuator - Temporary, Narrow [TL-3]	Energy Attenuator - Relocation, Narrow [TL-3]		SBEAT System [50:1 Flare]		Temporary Construction Barrier, Relocation		
Sub - Totals Brought Forward:	0	0	0	420		3	2		2		288		
14+138 - 14+201 (Offset 4.5m - 5.3m Lt)		63											
14+139 - 14+201 (Offset 4.5m - 5.3m Rt)		63											
14+201 - 14+221 (Offset 5.3m - 6.0m Lt)	20												
14+201 - 14+221 (Offset 5.3m - 6.0m Rt)	20												
14+260 - 14+280 (Offset 6.0m - 4.5m Lt)	20												
14+260 - 14+280 (Offset 6.0m - 4.6m Rt)	20												
14+280 - 14+302 (Offset 4.5m - 4.5m Lt)			22										
14+280 - 14+302 (Offset 4.6m - 4.5m Rt)			23										
14+302 - 14+341 (Offset 4.5m - 4.5m Lt)		39											
14+302 - 14+340 (Offset 4.5m - 4.5m Rt)		38											
14+430 Rt									1				
14+431 Lt									1				
Sub - Totals Carried Forward:	80	203	45	420		3	2		4		288		
	(P)	(P)	(P)	(P)		(P)	(P)		(P)		(P)		
TOTALS	80	203	45	420		3	2		4		288		
UNIT	m (P)	m (P)	m (P)	m (P)		each (P)	each (P)		each (P)		m (P)		
ITEM No.	120	121	122	123		124	125		126		127		

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_

SBGR & TCB

**QUANTITIES - MISCELLANEOUS 1**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
40

MINISTRY OF TRANSPORTATION - ONTARIO

Location and Position	Topsoil, Imported	Seed and Mulch Standard Roadside Mix Seeding	Light-Duty Silt Fence Barriers	Straw Bale Flow Check Dams	Bird Nesting Preventative Measures						References
Sub - Totals Brought Forward:											
Highway 101 Township of Chewett											
Nemegosenda River Bridge Site No. 46X-0215/B0											
On Bridge Structure					100 %						
Stage 2											
10+120 - 10+171 (Offset 32.2m Rt - 9.8m Lt)			59								
10+157 - 10+162 (Offset 34.5m Rt - 9.8m Lt)			55								
Final Road Construction											
14+039 - 14+234 Lt	125	2,497									
14+041 - 14+095 Rt	11	210									
14+067 (Offset 9.7m Lt)				1							
14+068 (Offset 9.4m Rt)				1							
14+105 - 14+219 Rt	51	1,020									
14+134 (Offset 15.2m Lt)				1							
14+137 (Offset 12.0m Rt)				1							
14+179 (Offset 16.8m Lt)				1							
14+248 - 14+438 Lt	78	1,558									
14+262 - 14+430 Rt	56	1,120									
14+421 Lt (Offset 10.0m Lt)				1							
Sub - Totals Carried Forward:	321	6,405	114	6	100 %						
		(P)	(P)	(P)							
<b>TOTALS</b>	321	6,405	114	6	100 %						
<b>UNIT</b>	m3	m2 (P)	m (P)	each (P)	lump sum						
<b>ITEM No.</b>	128	129	130	131	132						
<b>Reference</b>											

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_

Top Soil

**QUANTITIES - TEMPORARY INSTALLATION**

W.P. No. 5144-10-00  
Contract No. 2020-5153

Location	Structure/Equipment No.	Offset (m) to CL of Structure/Equip't (Note 1)	Signal Head Facing Direction	From - To OR Station	Distance (m)	5 m, Class - Wood Poles Direct Buried in Earth [Temporary] <sup>1</sup>	5 m, Class - Wood Poles Direct Buried in Rock [Temporary] <sup>1</sup>	Flasher Beacons [Temporary] [Detail] <sup>2</sup>	Riser Wires #12 AWG, 2/C	Portable Temporary Traffic Signals								
Sub - Totals Brought Forward:																		
Highway 101 Township of Chewett																		
Nemegosenda River Bridge Site No. 46X-0215/B0																		
Highway 101	PT1	7.2*	W	14+132						1								
Highway 101	PT2	7.8*	E	14+369						1								
Highway 101	P10	3.2*	W	13+889		1		1										
Highway 101	P11	3.2*	E	14+601			1	1										
Sub - Totals Carried Forward:						1	1	2	0	2								
						(P)	(P)	(P)		(P)								
TOTALS						1	1	2		2								
UNIT						each (P)	each (P)	each (P)	m (P)	each (P)								
ITEM No.						133	134	135		136								

MINISTRY OF TRANSPORTATION - ONTARIO

Temporary - Nemegosenda River Bridge

Remarks: 1. 150mm x 150mm x 5m Pressure Treated Wood Post.

2. 300mm Flasher Beacon with Solar Powered System.

Note: 1 When shown without \*, offset is from centre or control line of roadway.  
When shown with \*, offset is from edge of travelled pavement (EP).

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_













**QUANTITIES - HOT MIX AND GRANULAR**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
47

Description	Superpave 12.5 [Surface Course (40mm)]	Superpave 12.5 [Binder Course (40mm)]	Superpave 12.5 [Binder Course]	Granular A [Roadway]	Granular A [Temporary Detour]	Granular A [TMB Backfill & Padding]	Granular A [Structure Backfill]	Granular A [Concrete Curb and Gutter]		Granular B, Type II [Temporary Detour]	Granular B, Type II [Roaway]	Granular B, Type II [Bridge Backfill]	RAP Shouldering			References
Sub - Totals Brought Forward:																
Highway 101																
Township of Chapleau																
Sideburned Lake Bridge																
Site No. 46X-0015/B0																
Temporary Detour - Year 1																
Temporary Detour Bridge						1,072										
9+000 - 9+112					577					14						
9+167 - 9+329					1,314					616						
Final Road Construction																
Highway 101																
10+549 - 10+717				1,408							466					
10+549 - 10+718 Lt													95			
10+549 - 10+602 Lt (Left Shoulder)	8															
10+549 - 10+602 Cl (Lane)	37															
10+549 - 10+602 Rt (Right Shoulder)	8															
10+549 - 10+718 Rt													102			
10+602 - 10+718 Lt (Left Shoulder)	15		18													
10+602 - 10+718 Cl (Lanes)	82		101													
10+602 - 10+718 Rt (Right Shoulder)	15		18													
10+710 - 10+720 Rt								7								
Sideburned Lake Bridge																
10+718 - 10+763 Lt (Left Shoulder)	13	13														
10+718 - 10+763 Cl (Lanes)	32	32														
10+718- 10+763 Rt (Right Shoulder)	13	13														
Highway 101																
10+761 - 10+793 Rt								22								
10+761 - 10+793 Lt								22								
Sub - Totals Carried Forward:	223	58	137	1,408	1,891	1,072	0	51		630	466	0	197			

MINISTRY OF TRANSPORTATION - ONTARIO

TOTALS																
UNIT	t	t	t	t	t	t	t	t		t	t	t	m2			
ITEM No.		172			173						174		175			
Reference																

Remarks: \_\_\_\_\_

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_

Hot Mix and Granular





**QUANTITIES - HOT MIX AND GRANULAR**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
50

Description	Temporary Hot Mix Pavement																		References
Sub - Totals Brought Forward:																			
Hwy 101																			
Township of Chapleau																			
Sideburned Lake Bridge																			
Site No. 46X-0015/B0																			
Stage 2 - Temporary Detour																			
9+000 - 9+112	87																		
9+167 - 9+329	178																		
Sub - Totals Carried Forward:	265																		
<b>TOTALS</b>	265																		
UNIT	t																		
ITEM No.	178																		
Reference																			
Remarks:																			

MINISTRY OF TRANSPORTATION - ONTARIO

Temporary Hot Mix

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_







**QUANTITIES - MISCELLANEOUS 1**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
54

MINISTRY OF TRANSPORTATION - ONTARIO

Location and Position	Rock Protection	Rip-Rap (R-10)	Geotextile (Class II) (Non-woven) (FOS 75-150 micron)	Gabion Structures Not Exceeding 2 m Height							References
Sub - Totals Brought Forward:											
Highway 101											
Township of Chapleau											
Sideburned Lake Bridge											
Site No. 46X-0015/B0											
Temporary Modular Bridge											
9+110 - 9+113 (Offset 2.4m - 6.5m Rt)		12	17								
9+113 - 9+124 (Offset 3.2m - 6.5m Rt)	20		46								
9+110 - 9+113 (Offset 2.4m - 4.4m Lt)		6	8								
9+113 - 9+124 (Offset 2.4m - 4.4m Lt)	14		30								
9+160 - 9+166 (Offset 3.3m - 4.4m Lt)	8		17								
9+160 - 9+166 (Offset 2.3m - 4.5m Rt)	8		17								
9+166 - 9+169 (Offset 2.4m - 4.4m Lt)		6	8								
9+166 - 9+169 (Offset 2.3m - 4.4m Rt)		6	8								
West Detour Abutment			124								
East Detour Abutment			125								
Highway 101											
10+720 - 10+736 (Offset 6.7m - 12.3m Lt)	55		95								
10+720 - 10+737 (Offset 7.3m - 14.2m Rt)	55		100								
10+751 - 10+787 (Offset 6.5m - 11.1m Lt)	47		100								
10+752 - 10+761 (Offset 7.1m - 11.8m Rt)	22		40								
10+761 - 10+787 (Offset 7.3m - 9.7m Lt)			312	78							
10+788 (Offset 6.8m - 11.1m Lt)		7	14								
Sub - Totals Carried Forward:											
	229	37	1,061	78							
	(P)	(P)	(P)	(P)							
TOTALS											
UNIT	m3 (P)	m2 (P)	m2 (P)	m3 (P)							
ITEM No.	186	187	188	189							
Reference											
											CHKD. _____ APPR. _____ DATE _____

Rip-Rap & Geotextile





**QUANTITIES - MISCELLANEOUS 1**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
56

MINISTRY OF TRANSPORTATION - ONTARIO

Location and Position	Small Signs, Ground Mounted, New	Small Signs, Removal		Temporary Traffic Control Signs		Road Closing / Restriction Notice Signs (TC-64)							References
Sub - Totals Brought Forward:													
Highway 101													
Township of Chapleau													
Sideburned Lake Bridge													
Site No. 46X-0015/B0													
Throughout the Contract				100 %		4							
10+706 (G331)		1											
10+706 (G331(B))	1												
10+729 (Wa33R)		1											
10+760 (Wa33L)		1											
10+781 (G303)		1											
10+781 (G303)	1												
10+955 (N/A)		1											
10+955 (N/A)	1												
10+821 (G331)		1											
10+821 (G331(B))	1												
10+757 (Wa33R)		1											
10+726 (Wa33L)		1											
10+698 (N/A)		1											
10+698 (N/A)	1												
Sub - Totals Carried Forward:													
	(P) 5	(P) 9		100 %		(P) 4							
<b>TOTALS</b>	(P) 5	(P) 9		100 %		(P) 4							
<b>UNIT</b>	each (P)	each (P)		lump sum		each (P)							
<b>ITEM No.</b>	190	191		192		193							
<b>Reference</b>													
													CHKD. _____ APPR. _____ DATE _____



**QUANTITIES - MISCELLANEOUS 1**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
58

Location and Position	Single Rail SBGR with Channel [OPSD 912.315]	Single Rail SBGR, TL-3 [OPSD 912.185]	Single Rail SBGR, TL-3, Adjacent to 2H:1V Slope [OPSD 912.186]	Single Rail SBGR, TL-3, Adjacent to Curb and Gutter [OPSD 912.188]		TCB, Freestanding, Category II	Energy Attenuator - Temporary, Narrow [TL-3]	Energy Attenuator - Relocation, Narrow [TL-3]		SBEAT System [50:1 Flare]		Temporary Construction Barrier, Relocation	References
Sub - Totals Brought Forward:													
Highway 101													
Township of Chapleau													
Sideburned Lake Bridge													
Site No. 46X-0015/B0													
Stage 1													
10+621 Rt (On Concrete Pad)								1					
10+621 - 10+893 Rt						272							
10+893 Rt (On Concrete Pad)								1					
Stage 2													
Temporary Detour													
9+018 Rt (On Concrete Pad)													
9+018 - 9+110 Rt												92	
9+019 Lt (On Concrete Pad)								1					
9+019 - 9+110 Lt												92	
9+169 TMB - 10+ 893 Rt Hwy 101								1					
10+893 Rt (On Concrete Pad)						32						88	
9+169 TMB - 10+884 Hwy 101 Rt						112							
Final Road Construction													
10+696 Rt										1			
10+696 - 10+700 (Offset 5.3m Rt)			4										
10+700 - 10+720 (Offset 5.5m - 6.0m Rt)	20												
10+720 Lt										1			
10+700 - 10+720 (Offset 5.7m - 6.1m Lt)	20												
10+761 - 10+781 (Offset 6.1m - 5.7m Rt)	20												
10+781 - 10+793 (Offset 5.7m Rt)					12								
10+793 - 10+813 Rt (Offset 5.7m - 5.0m Rt)			18										
10+813 Rt										1			
10+761 - 10+781 (Offset 6.1m - 6.0m Lt)	20												
Sub - Totals Carried Forward:													
	(P)	(P)	(P)	(P)		(P)	(P)	(P)		(P)		(P)	
TOTALS													
UNIT	m (P)	m (P)	m (P)	m (P)		m (P)	each (P)	each (P)		each (P)		m (P)	
ITEM No.	198	199	200	201		202	203	204		205		206	
Reference													
													CHKD. _____ APPR. _____ DATE _____

MINISTRY OF TRANSPORTATION - ONTARIO

Guide Rail and TCB



**QUANTITIES - MISCELLANEOUS 1**

W.P. No. 5144-10-00  
Contract No. 2020-5153

SHEET  
60

MINISTRY OF TRANSPORTATION - ONTARIO

Location and Position	Topsoil, Imported	Seed and Mulch Standard Roadside Mix Seeding	Light-Duty Silt Fence Barriers	Straw Bale Flow Check Dams	Bird Nesting Preventative Measures						References
Sub - Totals Brought Forward:											
Highway 101 Township of Chapleau											
Sideburned Lake Bridge Site No. 46X-0015/B0											
On Bridge Structure					100 %						
Throughout Contract Limits											
10+548 - 10+720 Rt	55	1,105									
10+810 - 10+932 Rt	38	752									
10+548 - 10+720 Lt	26	514									
10+616 (Offset 7.5m Rt)				1							
10+638 (Offset 6.8m Lt)				1							
10+669 (Offset 7.7m Rt)				1							
10+670 (Offset 7.5m Lt)				1							
10+691 (Offset 8.4m Lt)				1							
10+715 (Offset 8.5m Lt)				1							
10+716 - 10+735 (Offset 20.0m - 6.7m Lt)			27								
10+722 - 10+734 (Offset 21.5m - 6.7m Rt)			22								
10+752 - 10+806 (Offset 6.5m - 11.9m Lt)			56								
10+755 - 10+798 (Offset 6.8m - 15.4m Rt)			49								
10+761 - 10+910 Rt	51	1,017									
Sub - Totals Carried Forward:	170	3,388	154	6	100 %						
		(P)	(P)	(P)							
TOTALS											
UNIT	m3	m2 (P)	m (P)	each (P)	lump sum						
ITEM No.	207	208	209	210	211						
Reference											

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_

Top Soil



**QUANTITIES - TEMPORARY INSTALLATION**

W.P. No. 5144-10-00  
Contract No. 2020-5153

Location	Structure/Equipment No.	Offset (m) to CL of Structure/Equip't (Note 1)	Signal Head Facing Direction	From - To OR Station	Distance (m)	Maintenance and Operation for Temporary Traffic Signal System Work	#2 AWG, 2-Cond., NSF-F-2 Low Voltage Cables, Aerial with ACSR Neutral [Temporary]	#6 AWG Low Voltage Cables Aerial on Messenger Cable [Temporary]	12-Cond. Traffic Signal Cables Aerial on Messenger Cable [Temporary]	7 mm, Grade 110 Steel Messenger Cables Aerial [Temporary]	9 mm, Grade 160 Steel Messenger Cables Aerial [Temporary]	#6 AWG, Insulated, Ground Wire [Temporary]	#6 AWG, Bare, Ground Wire [Temporary]	#2/0 AWG, Bare, Ground Wire [Temporary]	Ground Electrodes [Temporary] [Rods]	Supply Control Cabinet Assemblies [Temporary] Type 3, 1Ph 120/240 V, [OPSD 2441.000]	14 m, Class 3 Wood Poles Direct Buried in Rock [Temporary]	12.5 m, Class 4 Wood Poles Direct Buried in Rock [Temporary]
Sub - Totals Brought Forward:																		
Highway 101 Township of Chapleau																		
Sideburned Lake Bridge Site No. 46X-0015/B0						100 %												
Highway 101	P12	10.5		10+988										20	4	1		1
Highway 101	P13	8.9		10+942														1
Highway 101	P14	7.2		10+877.3														1
Highway 101	P15	9.7		10+877.3									1		1			1
Highway 101	P16	11.3		10+810														1
Highway 101	P17	12.7		10+720														1
Highway 101	P18	13.4		10+680														1
Highway 101	P19	8.8		10+633.6									1		1			1
Highway 101	P20	6.9		10+633.6									1		1			1
Highway 101	P21	3.2*	W	10+402														
Highway 101	P22	3.2*	E	11+108														
Highway 101				EP2-P12	12		12											
Highway 101				P12-P13	46			184		46	46							
Sub - Totals Carried Forward:						100 %	12	184	0	0	46	46	3	20	7	1	4	5
							(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)
TOTALS																		
UNIT						lump sum	m (P)	m (P)	m (P)	m (P)	m (P)	m (P)	m (P)	m (P)	each (P)	each (P)	each (P)	each (P)
ITEM No.						212	213	214	215	216	217	218	219	220				
Remarks:						Note: 1 When shown without *, offset is from centre or control line of roadway. When shown with *, offset is from edge of travelled pavement (EP).										CHKD. _____ APPR. _____ DATE _____		

MINISTRY OF TRANSPORTATION - ONTARIO

Temporary - Sideburned Lake Bridge



**QUANTITIES - TEMPORARY INSTALLATION**

W.P. No. 5144-10-00

Contract No. 2020-5153

Location	Structure/Equipment No.	Offset (m) to CL of Structure/Equip't (Note 1)	Signal Head Facing Direction	From - To OR Station	Distance (m)	5 m, Class - Wood Poles Direct Buried in Rock [Temporary] <sup>1</sup>	Guy Anchors (Temporary)	400W HPS Luminaire, 120 V Ballast c/w 200 W HPS Lamp [Temporary]	2.4 m Al. Tapered Elliptical Bracket	#12 AWG Riser Wires 3 Wires/Pole	Highway Type Signal Heads (Temporary) <sup>2</sup>	Riser Wires #14 AWG, 5/C	Flasher Beacons [Temporary] [Detail] <sup>3</sup>	Riser Wires #12 AWG, 2/C	Traffic Signal Controllers [Temporary] [OPSD 2510.010 & MTOD 2510.010] <sup>4</sup>	Non-Intrusive Detection System (Temporary)	Non-Intrusive Detectors	Non-Intrusive Detection Cables <sup>5</sup>	
Sub - Totals Brought Forward:																			
Highway 101 Township of Chapleau																			
Sideburned Lake Bridge Site No. 46X-0015/B0																	1		
Highway 101	P12	10.5		10+988			1												
Highway 101	P13	8.9		10+942															
Highway 101	P14	7.2		10+877.3			2								1				
Highway 101	P15	9.7		10+877.3			2	1	1	5							1	23	
Highway 101	P16	11.3		10+810															
Highway 101	P17	12.7		10+720															
Highway 101	P18	13.4		10+680			2												
Highway 101	P19	8.8		10+633.6			2												
Highway 101	P20	6.9		10+633.6			1	1	1	5							1	285	
Highway 101	P21	3.2*	W	10+402		1							1						
Highway 101	P22	3.2*	E	11+108		1							1						
Highway 101				EP2-P12	12														
Highway 101				P12-P13	46														
Sub - Totals Carried Forward:						2	10	2	2	10	0	0.0	2	0	1	1	2	308	
						(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	
TOTALS																			
UNIT						each (P)	each (P)	each (P)	each (P)	m (P)	each (P)	m (P)	each (P)	m (P)	each (P)	each (P)	each	m	
ITEM No.							221	222			223		224		225	226			
Remarks: 1. 150mm x 150mm x 5m Pressure Treated Wood Post.						2. All 300mm Lenses in Diameter.						Note: 1 When shown without *, offset is from centre or control line of roadway. When shown with *, offset is from edge of travelled pavement (EP).						CHKD. _____	
3. 300mm Flasher Beacon with Solar Powered System.						4. Traffic Signal Controller c/w UPS System.												APPR. _____	
5. Non-Intrusive Detection Cable as per Manufacturer's Recommendations.																		DATE _____	

MINISTRY OF TRANSPORTATION - ONTARIO

Temporary - Sideburned Lake Bridge

**QUANTITIES - TEMPORARY INSTALLATION**

W.P. No. 5144-10-00

Contract No. 2020-5153

Location	Structure/Equipment No.	Offset (m) to CL of Structure/Equip't (Note 1)	Signal Head Facing Direction	From - To OR Station	Distance (m)	Maintenance and Operation for Temporary Traffic Signal System Work	#2 AWG, 2-Cond., NSF-2 Low Voltage Cables, Aerial with ACSR Neutral [Temporary]	#6 AWG Low Voltage Cables Aerial on Messenger Cable [Temporary]	12-Cond. Traffic Signal Cables Aerial on Messenger Cable [Temporary]	7 mm, Grade 110 Steel Messenger Cables Aerial [Temporary]	9 mm, Grade 160 Steel Messenger Cables Aerial [Temporary]	#6 AWG, Insulated, Ground Wire [Temporary]	#6 AWG, Bare, Ground Wire [Temporary]	#2/O AWG, Bare, Ground Wire [Temporary]	Ground Electrodes [Temporary] [Rods]	Supply Control Cabinet Assemblies [Temporary] Type 3, 1Ph 120/240 V, [OPSD 2441.000]	14 m, Class 3 Wood Poles Direct Buried in Rock [Temporary]	12.5 m, Class 4 Wood Poles Direct Buried in Rock [Temporary]
Sub - Totals Brought Forward:						100 %	12	184	0	0	46	46	3	20	7	1	4	5
Highway 101				P13-P14	65			260			65	65						
Highway 101			E	P14-P15	17			34	17	17	17							
Highway 101				P15-P16	68			136	68		68							
Highway 101				P16-P17	90			180	90		90							
Highway 101				P17-P18	40			80	40		40							
Highway 101				P18-P19	48			96	48		48							
Highway 101			W	P19-P20	16			32		16	16							
Sub - Totals Carried Forward:						100 %	12	1,002	263	33	390	111	3	20	7	1	4	5
										33	390	111	3	20			4	5
										(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)	(P)
<b>TOTALS</b>						100 %	12	1,002	263		423		134		7	1		11
<b>UNIT</b>						lump sum	m (P)	m (P)	m (P)	m (P)	m (P)	m (P)	m (P)	m (P)	each (P)	each (P)	each (P)	each (P)
<b>ITEM No.</b>						212	213	214	215		216		217		218	219		220

MINISTRY OF TRANSPORTATION - ONTARIO

Temporary - Sideburned Lake Bridge

Remarks:

Note: 1 When shown without \*, offset is from centre or control line of roadway. When shown with \*, offset is from edge of travelled pavement (EP).

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_

**QUANTITIES - TEMPORARY INSTALLATION**

W.P. No. 5144-10-00

Contract No. 2020-5153

Location	Structure/Equipment No.	Offset (m) to CL of Structure/Equip't (Note 1)	Signal Head Facing Direction	From - To OR Station	Distance (m)	5 m, Class - Wood Poles Direct Buried in Rock [Temporary] <sup>1</sup>	Guy Anchors (Temporary)	400W HPS Luminaire, 120 V Ballast c/w 200 W HPS Lamp [Temporary]	2.4 m Al. Tapered Elliptical Bracket	#12 AWG Riser Wires 3 Wires/Pole	Highway Type Signal Heads (Temporary) <sup>2</sup>	Riser Wires #14 AWG, 5/C	Flasher Beacons [Temporary] [Detail] <sup>3</sup>	Riser Wires #12 AWG, 2/C	Traffic Signal Controllers [Temporary] [OPSD 2510.010 & MTOD 2510.017] <sup>4</sup>	Non-Intrusive Detection System (Temporary)	Non-Intrusive Detectors	Non-Intrusive Detection Cables <sup>5</sup>
Sub - Totals Brought Forward:						2	10	2	2	10	0	0.0	2	0	1	1	2	308
Highway 101				P13-P14	65													
Highway 101			E	P14-P15	17						2	14.0						
Highway 101				P15-P16	68													
Highway 101				P16-P17	90													
Highway 101				P17-P18	40													
Highway 101				P18-P19	48													
Highway 101			W	P19-P20	16						2	18.0						
Sub - Totals Carried Forward:						2	10	2	2	10	4	32.0	2	0	1	1		
						2		2					2					
						(P)	(P)	(P)		(P)			(P)		(P)	(P)		
TOTALS							10	2			4		2		1	1	2	308
UNIT						each (P)	each (P)	each (P)	each (P)	m (P)	each (P)	m (P)	each (P)	m (P)	each (P)	each (P)	each	m
ITEM No.							221	222			223		224		225	226		

MINISTRY OF TRANSPORTATION - ONTARIO

Temporary - Sideburned Lake Bridge

Remarks: 1. 150mm x 150mm x 5m Pressure Treated Wood Post.

3. 300mm Flasher Beacon with Solar Powered System.

5. Non-Intrusive Detection Cable as per Manufacturer's Recommendations.

2. All 300mm Lenses in Diameter.

4. Traffic Signal Controller c/w UPS System.

Note: 1 When shown without \*, offset is from centre or control line of roadway. When shown with \*, offset is from edge of travelled pavement (EP).

CHKD. \_\_\_\_\_  
APPR. \_\_\_\_\_  
DATE \_\_\_\_\_



