

QUANTITY SHEETS

CONTRACT NO. 2020-4090

ADDENDUM NO. 1

QUANTITIES - MISCELLANEOUS 1

W.P. No. 4013-19-00
Contract No. 2020-4090 (addendum 1)

SHEET
16

MINISTRY OF TRANSPORTATION - ONTARIO

Location and Position	Pavement Marking [Solid] [Yellow, 10 cm]	Pavement Marking [Solid] [White, 10 cm]	Pavement Marking [3-9-3] [White, 10 cm]	Pavement Marking [Solid] [White, 20 cm]	Pavement Marking [3-3-3] [White, 20 cm]								References
Sub - Totals Brought Forward:													
Town of Greater Napanee													
Highway 401 Westbound													
Fredericksburgh Twp.													
10+433 - 10+443 Lt					10								
10+443 - 10+493 Lt				100									
10+443 - 10+493 Lt				100									
10+493 - 10+621 Lt		128											
10+621 - 10+688 Lt				134									
10+621 - 10+688 Lt				134									
10+688 - 10+738 Rt	50												
10+688 - 10+738 Cl			13										
10+688 - 10+738 Lt					50								
10+688 - 10+738 Lt				100									
10+890 - 10+971 Lt					81								
10+890 - 11+100 Lt				420									
Highway 401 Eastbound													
Fredericksburgh Twp.													
10+316 - 10+326 Rt					10								
10+326 - 10+434 Rt				216									
10+326 - 10+434 Rt				216									
Sub - Totals Carried Forward:													
	50	128	13	1,420	151								
	(P)	(P)	(P)	(P)	(P)								
TOTALS													
UNIT	m (P)	m (P)	m (P)	m (P)	m (P)								
ITEM No.		31											
Reference													

CHKD. _____
APPR. _____
DATE _____

Addendum 1

QUANTITIES - MISCELLANEOUS 1

W.P. No. 4013-19-00
Contract No. 2020-4090 (addendum 1)

SHEET
17

MINISTRY OF TRANSPORTATION - ONTARIO

Location and Position	Pavement Marking [Solid] [Yellow, 10 cm]	Pavement Marking [Solid] [White, 10 cm]	Pavement Marking [3-9-3] [White, 10 cm]	Pavement Marking [Solid] [White, 20 cm]	Pavement Marking [3-3-3] [White, 20 cm]								References
Sub - Totals Brought Forward:	50	128	13	1,420	151								
10+434 - 10+538 Rt		104											
10+538 - 10+590 Rt				104									
10+538 - 10+590 Rt				104									
10+538 - 10+715 Rt				354									
10+590 - 10+600 Rt					10								
10+664 - 10+715 Lt	51												
10+664 - 10+715 Cl			13										
10+664 - 10+715 Rt					51								
10+664 - 10+715 Rt				102									
Sub - Totals Carried Forward:	101	232	26	2,084	212								
	101	232	26	2,084	212								
	(P)	(P)	(P)	(P)	(P)								
TOTALS		2,655											
UNIT	m (P)	m (P)	m (P)	m (P)	m (P)								
ITEM No.		31											